



# मोतीलाल नेहरू कॉलेज Motilal Nehru College



(दिल्ली विश्वविद्यालय)  
(University of Delhi)

संदर्भ : एमएनसी/बीजेएम  
Ref. : MNC/BJM/

Dated: 11.03.2024

## SHORT TENDER NOTICE

Sealed tender are invited for construction of Boundary wall in Playground at Motilal Nehru College. The Scope of work for the same in prescribed format is attached herewith. The tender should reach the college latest by 26<sup>th</sup> March, 2024 by 2.00pm.

On the top of the envelope, it should be written:-

**“TENDER FOR CONSTRUCTION OF BOUNDARY WALL AT MOTI LAL NEHRU COLLEGE”**

The envelope should be addressed to:

**The Principal, Motilal Nehru College, Benito Juarez Marg, New Delhi-110021**

**Bidders should enclosed the following documents with the tender:-**

1. Firm Company registration Certificate.
2. Experience certificates/work completion/work order etc. of last three years only.
3. Bank Details.
4. GST as applicable.
5. 5% earnest money be deposited with the tender through Demand Draft in favour of Principal, Motilal Nehru College as performance Security which shall be return to the bidder after sixty days from completion of work.

### **Term and conditions**

1. Warranty period will be one years, for any wear and tear. Contractor will provide its services without and charge.
2. Completion of work shall be 60 days from the date of receipt of order.
3. Corrigendum/addendum, if any, will be posted on college website well in time.


*Kashwan Sharma*  
11/3/2024  
**Officiating Principal**



**MOTILAL NEHRU COLLEGE: BENITO JUAREZ MARG: NEW DELHI: 110021**

**Tender for Construction of Boundary wall in Playground**

S No.	Item	unit	Quantity	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Hard rock (blasting prohibited)	Cub. Mtr	40		
2	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	Cub. Mtr	40		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.1 Cement mortar 1:4 (1 cement : 4 coarse sand) cum 7809.25				
3.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cub. Mtr	60		
4	20 mm cement plaster of mix :				
4.1	(1 cement: 6 coarse sand)	Sqr. Mtr	180		
5	Providing and laying the dry brick blast up to 100 mm before laying the laying in position cement concrete of specified grade	Sqr Mtr	65		
6	Providing and laying in position cement concrete of specified grade excluding the cost of cantering and shuttering - All work up to plinth level :	Cub. Mtr	12		
7	Centering and shuttering with 12mm thick shuttering plywood conforming to IS 4990:2011 and removal of form at all heights. Plywood will be supported on lock bars. 26.64.1 Suspended floors, roofs, landings, balconies and access platform	Sqr Mtr	20		
8	Providing and fixing 22-25 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, finish				



*Yashwanth Sharma*  
11/31/2024  
कार्यवाहक प्राचार्य

	etc. complete at all levels.				
8.1	Granite Zed black	Sqr. Mtr.	68		
8.2	Providing edge moulding to 22-25 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.	Meter	110		
9	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.(Make: Kajaria/Somany)	Sqr. Mtr	160		
10	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	Cub. Mtr	20		
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars	KG	1250		
	<b>Total</b>				

*Yogendra Sharma*  
11/3/2024

**Officiating Principal**

